

FULL HEIGHT DUCT PANELS

- **Manufacturer**
Decra Ltd, 34 Forest Business Park, Argall Avenue, London E10 7FB
Tel: 020 8520 4371 Fax: 020 8521 0605 email: sales@decraltd.co.uk
- **Reference**
Streamline duct panelling. (type DL)
To be compatible with the Streamline cubicle system.
- **Panels**
3 no. lift-off panels to run from floor to 1200mm high, allowing for 100mm skirting.
 - Panel material**
13mm o/a compact grade laminate (solid laminate) from manufacturer's standard choice of 23 colours.
 - Edging**
Black, self-edged, finished and bevelled
- **Method of fixing panels**
Lift-off secret-fixing clips to suit Decra system
- **Joint treatment**
As per drawing
 - a) Horizontal joints between panels to show min 25mm flashgap.
 - b) Vertical joints to suit design module; minimum flashgap 70mm where cubicle partitions abut.
- **Flashgaps**
High-pressure laminate strip fixed to softwood framework. Colour to be from manufacturer's standard choice of 23 colours.
- **Other requirements**
PAR softwood framework by main contractor, to include 100mm high plywood skirting. Allow for extra bracing to support urinals, washbasins and cisterns.
- **Options at extra cost**
Decra-triaqua modular cistern, urinal or washbasin frames